

LAMAR COUNTY BOARD OF COMMISSIONERS - BID SHEETS

RFB PKG NO. 2011-02

Removal of Designated Leaners, Hangers, and Stumps from Right of Way along several County Roads

Note: As of June 6th, 2011 the quantities are based on actual counts that have been approved by FEMA. Trees and stumps identified in this effort are marked by a white dot on the edge of the road and a white mark painted on the tree or stump.

LINE NO	ITEM DESCRIPTION	UNITS	UNIT PRICE DOLLARS/CENTS
1	<u>Hazardous Trees</u> – 91 trees have been identified by the County and are designated to be cut down. These trees will be cut off flush with the ground or as close to it as practicable.	Per tree	
A	___ trees < 8” diameter – Fee to cut tree and remove it to the disposal site. See details in #5 below.	Less than 8” diameter	\$/Tree
B	___ trees between 8” and 18” diameter – Fee to cut tree and remove it to the disposal site. See details in #5 below.	8” - 18” diameter	\$/Tree
C	___ trees between 18’ and 24” diameter – Fee to cut tree and remove it to the disposal site. See details in #5 below.	18” - 24” diameter	\$/Tree
D	___ trees > 24” diameter – Fee to cut tree and remove it to the disposal site. See details in #5 below.	More than 24” diameter	\$/Tree
2	<u>Hazardous Stumps</u> – Stumps have been evaluated by the County and hazardous stumps are designated to be removed	Per stump	
A	6 Stump designated for hauling and disposal. Price includes loading, hauling, and dumping costs. Other costs are included in #6 below	Less than 24” in diameter	\$/stump
B	10 Stumps designated for hauling and disposal. Price includes loading, hauling, and dumping costs. Other costs are included in #6 below.	Over 24” in diameter	\$/stump
3	<u>Hangers</u> – Hangers are considered any hanging/damaged branch or portion of the tree 2” or greater in diameter remaining in the tree(s) above the ROW. The County has identified 74 trees containing hangers that must be removed. Removal of hangers will be priced per tree regardless of how many hangers exist in each tree.	Per tree	\$/tree
4	<u>Leaners</u> – 43 trees leaning over the right of way have been identified by the County for removal of a portion of the tree. The Contractor will draw an imaginary line up from the right of way and cut the tree where it intersects this line.	Per tree	\$/tree
5	Disposal of debris – Contractor will remove all debris created by the removal of leaners, hangers, hazardous trees, and stumps. Such debris will be deposited at the Disposal Site at Cedar Grove Landfill.	N/A	Loading, hauling, and dumping costs are included in the price of this contract. The contractor will not have to weigh this debris, just deposit it in the designated location.

6	<p><u>Fill Dirt</u> – 2 stump holes have been identified by the County for refilling. The Contractor shall place compatible fill dirt in holes created by removal of hazardous stumps and other areas that pose an imminent and significant threat to public health and safety. Dirt is available for this purpose at the County recreation facility on Gordon Road. There will be no charge to the contractor but they must load and haul this dirt if they choose to use it.</p>	Per stump hole	\$/stump hole
7	Mobilization and demobilization	Lump Sum	\$/contract
8	Turf re-establishment along entire project – Contractor must smooth out any ruts they create and smooth the Right of Way enough to permit rotary mowing later in the Summer.	N/A	Turf re-establishment and final grading of ditches is not part of this Contract. Contractor will take reasonable precautions to protect right of way
9	Monitors are required to observe and report on activities at the collection and disposal site. Contractor agrees to allow monitor access to equipment and sufficient time as necessary to accomplish their duties of verifying load content and documenting validation activities.	N/A	Contractor will allow visual access by monitors at all times. This price is included in the overall bid amount.